
# **Code Commit (build project)**

# 1. Create Project Files


• https://github.com/samikshakotwal/3-tier-project-1.git



## 2. Create a CodeBuild Project

- Go to AWS Console > CodeBuild > Create Build Project.
- Project Name: my-web-app
- Source Provider: AWS CodeCommit
- Repository: Choose your repo
  - Choose: GitHub
  - Click "Connect to GitHub"
- (Login and authorize AWS)
- Environment:
  - OS: Amazon Linux 2
  - o Runtime: Choose your runtime (e.g., Node.js)
  - o Privileged: Checked if using Docker

- Service Role: Create new or choose existing IAM role
- Buildspec: Use buildspec.yml from source
- Artifacts: No artifacts or S3 (optional)
- Click "Create Build Project".




## 3. Create buildspec.yml in Github

# version: 0.2 phases: install: commands: - echo "Installing frontend and backend via Docker builds..." - sudo yum install nginx -y - docker build -t frontend-image ./application-code/web-tier - docker build -t backend-image ./application-code/app-tier build: commands: - echo "Running Docker containers..." - docker run -d --name frontend-container -p 81:80 frontend-image - docker run -d --name backend-container -p 4000:4000 backend-image - echo "Docker containers started successfully." artifacts:

### files:

- appspec.yml
- scripts/\*
- application-code/web-tier/Dockerfile
- application-code/app-tier/Dockerfile




## 4. Go to application-code/web-tier/

• Create Dockerfile

```
# Stage 1: Build the React app
FROM public.ecr.aws/docker/library/node:18 AS builder
WORKDIR /app
COPY package*.json ./
RUN npm install
COPY . .
RUN npm run build
# Stage 2: Serve with NGINX
FROM nginx:stable-alpine
# Remove default config
RUN rm /etc/nginx/nginx.conf
```


```
# copy our custom config
COPY nginx.conf /etc/nginx
# copy build output to NGINX web root
COPY --from=builder /app/build /usr/share/nginx/html
# Expose port
EXPOSE 80
```



## • Create nginx.conf

```
user nginx;
worker_processes auto;
error_log /var/log/nginx/error.log notice;
pid /run/nginx.pid;
include /usr/share/nginx/modules/*.conf;
events {
   worker_connections 1024;
}
http {
```

```
log format main '$remote addr - $remote user [$time local] "$request" '
          '$status $body_bytes_sent "$http_referer" '
          "$http user agent" "$http x forwarded for";
access_log /var/log/nginx/access.log main;
sendfile
               on:
tcp nopush
                 on;
keepalive timeout 65;
types hash max size 4096;
include
              /etc/nginx/mime.types;
                application/octet-stream;
default type
include /etc/nginx/conf.d/*.conf;
server {
  listen 80;
  server name localhost;
  location / {
    proxy_pass http://localhost:81; # Frontend
    proxy set header Host $host;
    proxy set header X-Real-IP $remote addr;
  location /api/ {
    proxy pass http://localhost:4000/; # Backend
    proxy_set_header Host $host;
    proxy set header X-Real-IP $remote addr;
```



## 5. Configure Project

- Then click "Start build"
- Monitor build logs to see progress

